



CENTERVILLE ROAD IMPROVEMENT PROJECT

DATE: May 31, 2018

SUBJECT: Centerville Road Construction Update #1
City Project No. 18-16
SAP 174-020-022 & SAP 062-659-018

The City of White Bear Lake awarded a contract to Forest Lake Contracting for the Centerville Road Improvement Project at the May 8, 2018 City Council Meeting. This project includes median installation and roadway widening along Centerville Road from Highway 96 north approximately 1,000 feet. A traffic signal will be installed at the Cub Foods and Lunds/Byerlys/White Bear Heights Apartments driveways, while the full-access intersection at Meadowlands Drive will be reconfigured to reduce vehicle conflicts and eliminate left turns from Centerville Road. Following widening, median, and signal work, Centerville Road will receive a mill and overlay from Highway 96 north ½-mile to the Canadian Pacific Railroad tracks.





Advance utility relocation work and utility potholing is anticipated to begin the week of June 4, with power pole relocation on the west side of Centerville Road, and underground utility modifications on the east side of Centerville Road. Periodic lane restrictions may occur during this advance work, and the trail on the west side of the roadway will be closed to facilitate a safe work zone.

Contracted roadway work is proposed to begin the week of June 25, 2018, and will occur in phases, as detailed on the following page. Each phase will take approximately 3-4 weeks to complete, and traffic on Centerville Road will be maintained in both directions with lane restrictions for the duration of the project.

The project is scheduled to be completed by the end of September, 2018. Periodic updates will be posted to the project website throughout the construction process.

Anticipated Project Staging

2018 to September 2018

LEGEND	
	WORK ZONE
	TEMPORARY TRAFFIC FLOW
	EXISTING TRAFFIC FLOW
	COMPLETED IN PREVIOUS STAGE

